

TYLin

Puentes Bataan–Cavite y Samuel De Champlain: Dos casos de estudio sobre el diseño y construcción de puentes emblemáticos

Alex Sanjines
T.Y. Lin International
alex.sanjines@tylin.com



Bataan–Cavite Interlink Bridge



De Medellín para el mundo: Conectando
saberes, construyendo futuro

Visión general del proyecto — Área Metropolitana de Manila


TYLin



De Medellín para el mundo: Conectando
saberes, construyendo futuro

Proyecto Bataan-Cavite Interlink Bridge

TYLin



Objetivos del Proyecto:


- Reducir el tiempo de viaje de 4-5 horas a 45 minutos.
- Conectar la masa continental de Bataan, al norte del Área Metropolitana de Manila, con Cavite, al sur del Área Metropolitana de Manila.
- Impulsar el crecimiento económico en ambas regiones.
- Habilitar el desarrollo de los puertos marítimos de Cavite y Bataan como principal puerta de acceso marítimo internacional a Filipinas.
- Proyecto emblemático del Programa de Infraestructura "Build Better More" (BBM).



De Medellín para el mundo: Conectando
saberes, construyendo futuro

Proyecto Bataan-Cavite Interlink Bridge

TYLin



SECCIÓN TRANSVERSAL

Descripción del proyecto:

- **Longitud total:** 32.15 km.
- **Tipología:** Segundo puente **atirantado** más largo del Sudeste Asiático; y uno de los 10 vanos más largos de puentes atirantados en el mundo (vano principal de **900 m**).
- **Capacidad vial:** 4 carriles (2 por sentido) con **hombros/acotamientos**.
- **Extremo norte (cabecera norte):** Mariveles, Bataan.




De Medellín para el mundo: Conectando
saberes, construyendo futuro

Aspectos clave


TYLin

- Vida de diseño: 100 años.
- Puesta en servicio (apertura al tráfico): ~2031.
- Inversión estimada: PHP 219.3 mil millones ($\approx$ USD 3.9 mil millones)
- Propósito: Proveer una solución de puente segura y eficiente que refleje los valores y las características únicas de Filipinas y de su gente.



De Medellín para el mundo: Conectando
saberes, construyendo futuro

El proyecto está segmentado en paquetes de contratación TYLin




De Medellín para el mundo: Conectando
saberes, construyendo futuro

Bataan-Cavite: South Channel Bridge




South Channel Crossing

Bataan-Cavite: South Channel Bridge



South Channel Bridge


TYLin



De Medellín para el mundo: Conectando
saberes, construyendo futuro

Typical Deck Section - Orthotopic Deck

TYLin




De Medellín para el mundo: Conectando
saberes, construyendo futuro

Tower Caisson – Dry Dock Construction

TYLin

Caisson Construction

- STEP 1. INSTALL THE FALSEWORK FOR CAISSON BOTTOM SLAB.
- STEP 2. INSTALL THE REBAR CAGES FOR BOTTOM SLAB, OUTER RIBS, OUTER WALL AND CONE WALL.
- STEP 3. CAST IN PLACE THE BOTTOM SLAB WITH OUTER WALL, CONE WALL, 20 NOS. OUTER RIBS AS SHOWN WITH TOP SLAB.




De Medellín para el mundo: Conectando
saberes, construyendo futuro

Tower Caisson – Dry Dock Construction

TYLin

Caisson Construction



De Medellín para el mundo: Conectando
saberes, construyendo futuro


Tower Caisson – Wet Dock Construction

Caisson Float-out to Wet Dock

TYLin



Rion-Antirion Bridge



De Medellín para el mundo: Conectando
saberes, construyendo futuro


Tower Caisson – Wet Dock Construction

Caisson Construction at Wet Dock

TYLin



Rion-Antirion Bridge



De Medellín para el mundo: Conectando
saberes, construyendo futuro

Tower Caisson Erection– Site Preparation

TYLin

Seabed Dredging



Rion-Antirion Bridge

Inclusion Pile Driving to reinforce seabed



Rion-Antirion Bridge



De Medellín para el mundo: Conectando
saberes, construyendo futuro

Tower Caisson – Erection @ Site



TYLin

Caisson Erection

Step 1: Excavate the top of seabed
soil and prepare pile template

Step 2: Drive and Install all
inclusion piles

Step 3: Place the Gravel Fill



De Medellín para el mundo: Conectando
saberes, construyendo futuro

Tower Caisson - Construction

TYLin



Caisson Erection

Step 4: Float the pre-fabricated caisson in place

Step 5: Stabilize Caisson using stabilizing barges and tugboats



Rion-Antirion Bridge



De Medellín para el mundo: Conectando
saberes, construyendo futuro



Tower Caisson - Construction

TYLin



Caisson Erection

Step 6: Sink Caisson to bottom of seabed with temporary ballast weight as needed to sink the caisson until it lands at top of gravel

Step 7: Cast the remaining upper cone wall after caisson landing at seabed.



Rion-Antirion Bridge



De Medellín para el mundo: Conectando
saberes, construyendo futuro



Tower Caisson - Foundation

TYLin


Caisson Erection

Step 8: Cast the remaining inner ribs and inner walls

Step 9: Remove temporary ballast and place permanent ballast per design

Step 10: Install scour protection

Step 11: Proceed with tower segment erection




De Medellín para el mundo: Conectando
saberes, construyendo futuro



SCB Tower Erection

TYLin





De Medellín para el mundo: Conectando
saberes, construyendo futuro

SCB Superstructure Fabrication

TYLin

Orthotropic Box Girder (OBG) – Typical Segment Fabrication

Cross Beam Section




De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

SCB Superstructure Fabrication

Orthotropic Box Girder (OBG) – Typical Segment Fabrication



Parts & Subassemblies




Setting up jigs



TYLin


SCB Superstructure Erection



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin


SCB Superstructure Erection



De Medellín para el mundo: Conectando
saberes, construyendo futuro

North Channel Bridge (NCB)


TYLin



De Medellín para el mundo: Conectando
saberes, construyendo futuro

Typical Deck Section: Composite Deck

TYLin





De Medellín para el mundo: Conectando
saberes, construyendo futuro


Tower & Anchor Pier Caissons – Dry/Wet Dock Construction

Similar to South Channel Bridge

TYLin



Rion-Antirion Bridge




Anchor Pier Caisson

De Medellín para el mundo: Conectando
saberes, construyendo futuro

Tower Caisson

Superstructure Erection

TYLin



Stage 1

1. Construct foundations, towers, and anchor piers
2. Place Pier Table (segment NT/ST) on Temporary Supports
3. Engage Transverse/Longitudinal Restraints
4. Install Cables NN-C01B/NN-C01M
5. Cast Pier Table (segment NT/ST) Deck Concrete
6. Adjust cables NN-C01B/NN-C01M
7. Remove temporary supports



Port Mann Bridge




De Medellín para el mundo: Conectando
saberes, construyendo futuro

Superstructure erection

TYLin

Stage 2

1. Erect Module Lifer and erect field segment NS01 steel with spider frame
2. Install cables NN-C02B and stress to initial load
3. Place NS01 Deck Panels
4. Tune/adjust cables NN-C02B
5. Pour NS01 Longitudinal and Transverse CIP joint between deck panels and along edge girders
6. Adjust cables NN-C02B
7. Erect NC01 similar to NS01 sequence steps 1 thru 6




De Medellín para el mundo: Conectando
saberes, construyendo futuro

Superstructure erection

TYLin

Stage 3

1. Erect NS02/NC02, NS03/NC03, NS04/NC04, and NS05 similar to sequence in stage 2 steps 1 thru 6.
2. Install temporary backspan pier
3. Erect NC05 similar to sequence in stage 2 steps 1 thru 6.





De Medellín para el mundo: Conectando
saberes, construyendo futuro

Superstructure erection

TYLin

Stage 4

1. Erect NS06/NC06, NS07/NC07, NS08/NC08, NS09/NS10/NC10, NS11/NC11 with spider frame similar to sequence in stage2 steps 1 thru 6
2. Erect field section NS12 steel and cast deck concrete
3. Erect field segment NC12 steel
4. Install cables NN-C13B and NN-C13M and stress to initial loads
5. Place NC12 deck panels
6. Tune/adjust cable NN-C13B and NN-C13M
7. Pour NC12 longitudinal and traverse CIP joints between deck panels and along edge girders
8. Composite adjust cables NN-C13B and NN-C13M
9. Erect NC13 and NC14 similar to NC12 with cables NN-C14B/NN-C14M and NN-C15B/NN-C15M



Gordie Howe Bridge



De Medellín para el mundo: Conectando
saberes, construyendo futuro

Marine Viaducts: Construction Driven Design

TYLin



60m span length

- Span-by-span precast segmental construction using overhead gantry will be used
- Adopted at shallow water areas with water depth <10m

100m span length

- Girders erected using precast full-span segments and floating cranes
- Adopted at deep water areas
- Minimizes schedule and construction cost of foundation and superstructure

133m span length


- Cast-in-place segmental balanced cantilever construction using form travellers
- Adopted at the span over the 100m-wide Nearshore Navigational Channel



De Medellín para el mundo: Conectando
saberes, construyendo futuro

Span Arrangement

TYLin



60m span modules ~ 8.9 km

100m span modules ~ 11.7 km


91m-133m-91m span module ~ 0.3 km



De Medellín para el mundo: Conectando
saberes, construyendo futuro

60m Span Module


TYLin




De Medellín para el mundo: Conectando
saberes, construyendo futuro

60m Span Module: *Box Girder Deck*

TYLin




- **Superstructure**
Precast Concrete Box
- **Rebar Grade**
Deformed Steel bar: Grade 420 MPa
- **Concrete Strength**
 $f'_c = 45 \text{ MPa}$ (Precast Segments and CIP joints)



De Medellín para el mundo: Conectando
saberes, construyendo futuro



Construction Sequence (Marine Viaduct) 60m span module (Phase 1)

TYLin



CIDH Pile Erection
using Reverse
Circulation Drilling

Pile Cap Erection
using Precast Slab
with sealed steel
wall forms




De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Construction Sequence (Marine Viaduct) 60m span module (Phase 3)



Pier Erection





De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Construction Sequence (Marine Viaduct) 60m span module (Phase 4)

Erection using Launching Truss




De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Construction Sequence (Marine Viaduct) 60m span module (Phase 5)

Lifting and positioning of each segment




De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Construction Sequence (Marine Viaduct) 60m span module (Phase 4)

Segment assembly and post-tensioning



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Construction Sequence (Marine Viaduct) 60m span module (Phase 7)

Launching of erection gantry

De Medellín para el mundo: Conectando
saberes, construyendo futuro

SIMPOSIO INTERNACIONAL
DE INGENIERIA DE PUENTES
SIIP 2025

Asociación de Ingenieros
Estructurales de Antioquia

TYLin


Construction Sequence (Marine Viaduct) 60m span module (Phase 8)

Finishing work

De Medellín para el mundo: Conectando
saberes, construyendo futuro

SIMPOSIO INTERNACIONAL
DE INGENIERIA DE PUENTES
SIIP 2025


Asociación de Ingenieros
Estructurales de Antioquia




100m Span Module: *Box Girder Deck*

TYLin

- **Superstructure**
Precast Concrete Box
- **Rebar Grade**
Deformed Steel bar: Grade 420 MPa
- **Concrete Strength**
 $f'_c = 45 \text{ MPa}$ (Precast Segments and CIP joints)



SECTION AT TYPICAL MIDSPAN



SECTION AT TYPICAL SUPPORT




De Medellín para el mundo: Conectando
saberes, construyendo futuro

Construction Sequence (Marine Viaduct) 100m span module (Phase 1)



TYLin

- Install permanent non-structural steel casing
- Excavation and cleaning the hole
- Place the reinforcement cage and pour the concrete for pile
- Install concrete precast shell
- Assemble reinforcement and pour the concrete for pile cap

Pile Cap Erection
using Precast Slab
with sealed steel
wall forms



CIDH Pile Erection
using Reverse
Circulation Drilling




De Medellín para el mundo: Conectando
saberes, construyendo futuro

Construction Sequence (Marine Viaduct) 100m span module (Phase 2)

TYLin

- Install steel form for pier shaft erection
- Assemble reinforcement and pour the concrete for pier
- Install thread bars for temporary fixing between pier table and pier cap
- Assemble reinforcement and pour the concrete for pier cap
- Install bearings on pier cap

Pier Erection



De Medellín para el mundo: Conectando
saberes, construyendo futuro

100m span Full Cantilever Fabrication


TYLin

- Precast Cantilever Span Casting (full span girder L = 98m)



Fabrication Sequence

- FABRICATION OF FULL SPAN GIRDER IN CASTING YARD
- STEP 1: PREPARED USING THE BALANCED CANTILEVER METHOD
- STEP 2: SECTIONS ARE CAST ON A SERIES OF PILES IN CASTING YARD
- STEP 3: ASSEMBLE REINFORCEMENT, POURING CONCRETE, STRESSING TENDONS
- STEP 4: MOVE TEMPORARY SUPPORT FORWARD USING SLIDE SYSTEM




De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Construction Sequence (Marine Viaduct) 100m span module (Phases 3 to 5)


- Prefabricated full span girder ($L = 98\text{m}$) is moved to site by marine heavy-lifting crane



Confederation Bridge



- Erection of Next Full Cantilever and cast Key Segment





De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Construction Sequence (Marine Viaduct) 100m span module (Phase 6)

Erection of remaining full cantilever spans and install end span segments

- Erect and position the prefabricated end span.
- Adjust final alignment of girders with alignment beam at end span segment and key segment.
- Cast key segment (side span and center span).
- Prestress the span tendons at mid span and end spans when the concrete stressing compressive strength has reached.
- Dismantle temporary supports and alignment beam




De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

100m span module (Phase 7)

Finishing Works

- Install expansion joint
- Install median and side barrier, pavement work
- Install maintenance pathway frame inside girder




De Medellín para el mundo: Conectando
saberes, construyendo futuro



91m-133m-91m Span Module @ Nearshore Channel

TYLin

Erection by Cast-in-Place Balanced Cantilever Construction





De Medellín para el mundo: Conectando
saberes, construyendo futuro

Superstructure 133m span

TYLin

- **Superstructure**
Cast-in-place Segmental Concrete Box
- **Rebar Grade**
Deformed Steel bar: Grade 420 MPa
- **Concrete Strength**
 $f'_c = 45$ MPa (Segments and CIP joints)




De Medellín para el mundo: Conectando
saberes, construyendo futuro

91m-133m-91m Span Module – Balanced Cantilever

TYLin

Erection of CIP Box Girder Segments

- Install CIP Form Travellers at both ends of Pier Table
- Stabilize Pier Table with temporary supports
- Install rebar and cast segments
- After concrete reaches strength, prestress the Cantilever tendons
- Advance the form travellers forward and repeat



De Medellín para el mundo: Conectando
saberes, construyendo futuro



Samuel De Champlain Bridge Corridor Project

TYLin

- Resumen del proyecto
- Criterios de diseño y desafíos específicos del sitio
- Durabilidad
- Construcción Acelerada de Puentes (ABC)
- Operación y Mantenimiento (O&M)



De Medellín para el mundo: Conectando
saberes, construyendo futuro

Samuel De Champlain Bridge Corridor Project


TYLin

Factoids:

- \$4.2 Billion CDN PPP (DBFOM) Project (\$1 CDN = \$0.77 USD)
- \$2.2 Billion CDN Design-Build Component
- Contract awarded June 2015
- Opened to vehicular traffic July 1, 2019
- Opened to light rail traffic July 2023

Our Role:


- Managing Partner of Bridge Design Joint-Venture
- Engineer-of-Record of the Cable-Stayed Bridge



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin


Project Location – Montreal, Canada



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Project Description – 3.4 km




De Medellín para el mundo: Conectando
saberes, construyendo futuro

Project Description

- 60 m in width
- 3 Corridor Design
 - 4 traffic lanes on Northbound and Southbound Highways
 - Transit corridor for Light Rail
 - Multi-use path for cyclists and pedestrians
- Lifeline bridge
- 125-year design life

TYLin



A = MULTIPLE-USE PATH
B = BUS LANE
C = HIGHWAY LANE
D = TRANSIT LANE
E = SHOULDER



De Medellín para el mundo: Conectando
saberes, construyendo futuro

Project Context and the Need for ABC

TYLin

1986

- First prestressed concrete girder repaired

1991 to 1992

- Replacement of the reinforced concrete deck by orthotropic steel deck

2011

- Federal Government announced replacement of a new bridge upon review of the feasibility studies



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Project Context and the Need for ABC

2013

- Reports indicated the old bridge was reaching the end of its useful life. Gov. of Canada announced that it would accelerate its replacement

Oct. 2013

- JCCBI closes a traffic lane after the appearance of a flexural crack at mid-span of an edge-girder

Dec. 2013 / May 2014

- Installation of emergency super-beam followed by emergency modular truss

Feb. 2014

- RFQ is issued followed by RFP in July 2014



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Need for Replacement

- One of North America's Busiest Crossings (60M vehicles per year)
- Original Bridge (Built 1962)
 - Exposure to de-icing salt
- High Maintenance Expense
 - Major rehabilitation works
 - From 2011-2016, more than \$300 M CDN over 6 years period
- Two lane closures incidences late 2013
 - Appearance of a flexural crack at mid-span of an edge-girder
 - Urgent need for replacement



Reference: Pre-feasibility Study of the Replacement of the Existing Champlain Bridge – Summary Report, March 31, 2011



De Medellín para el mundo: Conectando
saberes, construyendo futuro

Technical Challenges

- Extreme Temperature
 - Varying from -34°C (-29.2°F) to above 30°C (86°F)
- Ice accretion, Ice loading, Ice abrasion
- Wind, Seismic, Vessel Collision, Scour
- Channel Closure 4 months in a year
- “No Construction Zone” in Seaway
- Challenging field construction

TYLin




De Medellín para el mundo: Conectando
saberes, construyendo futuro




Design Criteria

- Scour
 - 100 year flood
 - Design for Scour Range
- Vessel Collision
 - Class 1 critical bridge
 - Vessel types that navigate through and adjacent to the Saint Lawrence Seaway
 - Maximum annual frequency of collapse of 1/10,000

TYLin



Bathymetry in Project Vicinity



Passing Vessel Transit Paths in Channel through Bridge




De Medellín para el mundo: Conectando
saberes, construyendo futuro



Wind Design - Wind Tunnel Studies

- Wind Climate Study
 - Design wind speeds (at deck height):
 - 20-year RP for construction = 27.5 m/s
 - 125 year RP for strength design = 33 m/s
 - 10,000 years for aerodynamic stability = 48 m/s
- 1 to 50 scale section models of deck & tower legs (WWL)
 - Static tests, aerodynamic derivative tests, Load Analyses – stable to 70 m/s
- Equivalent Static Load Analysis (BLWTL)
- 1 to 150 Scale Full Aeroelastic Model Tests (BLWTL)
 - Completed Bridge
 - Critical Cantilever Construction Stages

BLWTL = Boundary Layer Wind Tunnel Laboratory
 ARA = Applied Research Services Inc.
 WWL = West Wind Laboratory inc




TYLin



De Medellín para el mundo: Conectando
 saberes, construyendo futuro

Seismic Design

- Factor demands of 2475-year event by 1.3
- Capacity is the un-factored ultimate resistance
- Seismic detailing not required
- Material strain checks not required




TYLin



De Medellín para el mundo: Conectando
 saberes, construyendo futuro

Achieving 125-year Design Life

▪ Holistic Approach to Durability Plan



De Medellín para el mundo: Conectando
saberes, construyendo futuro

Design - Service Life Modeling


- Determine environmental exposure (i.e. de-icing salts)
- 4 Concrete mixes were specified. High performance mixes (with silica fume and fly ash) were used in areas most susceptible to exposure (i.e. superstructure)
- Supplemental corrosion protection system (i.e. calcium nitrate corrosion inhibitor)
- Rebar materials (i.e. stainless steel, galv steel)
- Concrete cover
- Probabilistic analysis (with use of STADIUM® modeling software) to estimate time-to-corrosion initiation

Input Variable	Mix 1	Mix 2	Mix 3	Mix 4
STADIUM Transport Properties¹				
Ion Diffusion Coefficient, IDC ($e^{-11} \text{ m}^2/\text{s}$)	1.0	2.0	3.0	4.0
Moisture Transport Coefficient, MTC ($e^{-22} \text{ m}^2/\text{s}$)	15	15	15	15
Porosity (%)	12.5	12.5	12.5	12.5
STADIUM Aging Parameters				
Hydration Parameter, a	1.00	1.00	1.00	1.00
Hydration Parameter, α	1.0000	1.0000	1.0000	1.0000
Maximum CSA A23.2-23C Acceptance Criteria during Production²				
Rapid Chloride Permeability, C	800	800	1000	1500



De Medellín para el mundo: Conectando
saberes, construyendo futuro

Fast-track Schedule



De Medellín para el mundo: Conectando
saberes, construyendo futuro

Accelerated Bridge Construction (ABC) in Mega Scale

Design for Accelerated Bridge Construction

- Maximize use of modular construction
- Precast concrete elements; minimize cast-in-place
- Pre-fabricated steel elements with field bolting
- Avoid delays due to severe cold weather
- Prefabrication provides for better quality control
- Efficient construction schedule



Credit: @ThomasHeinser



De Medellín para el mundo: Conectando
saberes, construyendo futuro


Maximize Use of Modular Construction - Foundations

Approaches:

- 33 total approach piers:
 - 25 West Approach:
 - 6 cast-in-place (CIP) spread footings
 - 19 precast marine foundations
 - 8 East Approach:
 - 4 CIP spread footings
 - 4 CIP pile caps with 8 – 1.2m (4') dia. cast-in-drilled hole (CIDH) piles

Cable-Stayed Bridge:


- 4 Total CSB piers and MST Tower:
 - W01/W02/E01: CIP pile caps with 6 – 1.2m (4') dia. cast-in-drilled hole (CIDH) piles ea.
 - E02: CIP spread footings
 - MST: CIP footing
 - 2 pile caps (pods). Pods are linked with tie beams
 - 2 x 21 - 1.2m (4') dia. piles each pod



De Medellín para el mundo: Conectando
saberes, construyendo futuro

Design - Optimizing Span Lengths in Approaches

- Concrete Option
 - Constant depth concrete girder
 - 60m spans, ~50 piers, but more foundations
- Steel Option
 - Constant depth steel girder (i.e. OGB)
 - 100m spans, ~30 piers, but costly
- Composite Option (Chosen)
 - 80m-84m spans, 37 piers
- Composite deck option for the superstructure has the best balance: saved time, cost, and reduced in-water works



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Heavy Lift Foundation Setting (Weight 600 ~ 1000 MT)



Credit: Infrastructure Canada

- Precast spread footing w/ pier starter
- Custom-built floating installer



- Sacrificial jacks for leveling/tremie concrete
- 2-3 days per foundation



De Medellín para el mundo: Conectando
saberes, construyendo futuro

Pier Bents


TYLin



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Precast Pier Bent




De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Pier Bents

- Prescribed architectural appearance per Definition Drawings
- Pier shapes are common to approaches and cable-stayed bridge
- Precast pier bent segments
- Post-tensioning tendons are used in pier legs
- Post-tensioning extends from W-frame down into footing loop tendons
- W-Frame anchored to piers via post-tensioning



De Medellín para el mundo: Conectando
saberes, construyendo futuro

Concrete Characteristics

(1 MPa = 145 psi, 60 MPa = 8702 psi)

Component	f'c	Characteristics	w/cm
Deck slab panels (cable stayed bridge)	70MPa	Precast	0.30
Deck slab panels (approach spans)	60 MPa	Precast	0.32
MST (Pylon) - shaft	60 MPa	Precast Lower/CIP Upper	0.30
MST (Pylon) – pile cap	35 MPa	Cast-in-Place (CIP)	0.38
Drilled shaft (deep foundation)	50 MPa	Tremie	0.38
Piers (columns – approach spans)	60 MPa (80 MPa)	Precast	0.32
Piers (footings – approach spans)	35 MPa	Precast	0.38



De Medellín para el mundo: Conectando
saberes, construyendo futuro



Pier Bents and Steel Pier Caps in Construction



Credit: Infrastructure Canada



De Medellín para el mundo: Conectando
saberes, construyendo futuro



TYLin

Steel Pier Cap Erection – Lift Weight > 200 MT




De Medellín para el mundo: Conectando
saberes, construyendo futuro

Steel Pier Cap Center Splice


TYLin

- Pier Cap with Steel Center Splice
 - Weight ~450 MT

- Pier Cap with Concrete Center Splice
 - Weight ~550 MT



Credit: Infrastructure Canada



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin


Cable-Stayed Bridge



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Cable-Stayed Bridge



De Medellín para el mundo: Conectando
saberes, construyendo futuro


TYLin

-





TYLin

-
- Figure 1: Plan view of the bridge deck cross-section. The diagram shows a cross-section of a bridge deck with a central rectangular opening. Dimensions are given in feet and inches. The total width is 61.56 feet. The width of the deck on either side of the opening is 9.09 feet. The total height is 78.34 feet. The height of the deck on either side of the opening is 11.00 feet. The width of the opening is 19.4 feet. The height of the opening is 25.6 feet. The thickness of the deck is 3.10 feet. The centerline of the bridge is indicated by a dashed line.




TYPICAL PRECAST SEGMENT WALL REINFORCING



TYLin

MST Lower Shafts Precast Segmental Construction



- 44 precast lower tower leg segments
- Weight ~ 77 MT
- Up to 3-4 segments erected per day
- Completed in ~40 days



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

MST Lower Shafts - Epoxy Joint Mockup & Testing



- Air tightness test conducted 2 days after epoxy
- No leak at the joint validated with soap water
- Pressure kept at 100 psi for 5 minutes with out any loss, as per PTI recommendation
- Drilled core @ 45 deg. showed epoxy on all surfaces
- Cores samples were tested for strength



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

MST Upper Shafts



- 15 cast-in-place upper shaft segments
- 1 lift cast every 2 weeks with jump forms



Credit: Infrastructure Canada



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

MST Upper Shafts – Link Beam



- Composite with tower segment
- Independent anchorages outside of tower
- Allows for modular construction





De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Link Beam – Integrated Shop Drawing

- 3-D integrated shop drawings
- Clash avoidance
- Initial investment in the design phase saves on construction time




De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Stay Cable

- 60 total stay cables
- Mainspan: 121-strand cables ea.
- Backspan: 127-strand cables ea.
- Stay is not grouted
- Corrosion protection provided by DSI:
 - Galvanized wire strand
 - Wax and Polyethylene (PE)-Coating
 - HDPE Sheathing
 - Water and airtight anchorage zones




De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Damping

- Every stay cable includes a twin tube hydraulic telescopic damper for vibration control
- Stay Cable Dampers are needed to mitigate the effects cause by the following sources of vibration:
 - Vortex shedding
 - Rain/wind induced vibrations (RWIV)
 - Galloping due to inclination
 - Wake galloping
 - Galloping due to ice accretion
 - Excitation from vibrations in other parts of the bridge
 - Buffeting from wind turbulences



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Wind Tunnel Testing - Full Aeroelastic Model Test



- With existing Champlain bridge and construction tower crane



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Stay Cable Testing

- Force Technology and National Research Council (NRC) – Canada
- Testing Program (samples – double helix / 200mm (8") rings / 300 mm (12") rings:
 - Static dry tests
 - Passive-dynamic tests with simulated rain
 - Static tests with ice accretion
 - Ice accretion and de-icing tests



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin


Superstructure



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Superstructure – Composite Steel Girder, Precast Deck Panels



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Superstructure – Fabrication in Spain



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Superstructure – Precast Deck Panels



- All deck reinforcement Duplex Stainless Steel: EN 1.4362 (UNS S32304) – 520 MPa (75.4 ksi)
- No. of Panels: 1400 (CSB)
- No. of Panels: 9638 Total
- Shop 1 – Northbound, Southbound panels 5 casting lines
- Shop 2 – Transit corridor 3 casting lines
- Produced up to 50 panels per week



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Superstructure – Precast Deck Panels


- 440 precast deck slab panels installed per week on-site.



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Accelerated Construction Methods – Large Segments




De Medellín para el mundo: Conectando
saberes, construyendo futuro

SSLC

TYLin

Superstructure Erection - MS1-Segment – 850 MT

- 60m (196'-10") x 12.5m (41') segments



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Superstructure Erection - MS1-Segment (Video)




De Medellín para el mundo: Conectando
saberes, construyendo futuro

newchamplain.ca/

CSB Construction Sequence


TYLin



De Medellín para el mundo: Conectando
saberes, construyendo futuro

CSB Construction Sequence


TYLin





De Medellín para el mundo: Conectando
saberes, construyendo futuro

CSB Construction Sequence – Original (MS15-E01)

TYLin




De Medellín para el mundo: Conectando
saberes, construyendo futuro



TYLin

Erection Analysis in RM: Option E''



De Medellín para el mundo: Conectando
saberes, construyendo futuro

Alternative Erection Scheme Implemented (2 Months Saved)

TYLin




King Post Tower (11-01-2018)

Credit: Infrastructure Canada



King Post Tower (12-10-2018)



Alignment of MS11, MS12 (02-11-2019)



De Medellín para el mundo: Conectando
saberes, construyendo futuro


TYLin

Operation – Maintenance Access Plan

- Under-bridge Inspection Vehicle
- Under-bridge Maintenance Gantry
- Walkways
- Electric Shuttle Vehicle
- Inspection Cradle
- Rope Access System
- Elevator
- Ladders
- Platforms
- Unmanned Inspection Vehicle
- Stay Cable Gantry
- Cross Passage Platform



Shuttleway




De Medellín para el mundo: Conectando
saberes, construyendo futuro

Credit: Infrastructure Canada

TYLin

Structural Health Monitoring



De Medellín para el mundo: Conectando
saberes, construyendo futuro

Credit: Infrastructure Canada

TYLin

Accelerated Bridge Construction (ABC) in Mega Scale (Recap)

Design for Accelerated Bridge Construction

- Maximize use of modular construction
- Precast concrete elements; minimize cast-in-place
- Pre-fabricated steel elements with field bolting
- Avoid delays due to severe cold weather
- Prefabrication provides for better quality control
- Efficient construction schedule



Credit: @ThomasHeinser



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Takeaways

- Meeting Architectural Vision and satisfying community expectations via Definition Design within a Design-Build, PPP framework. This method worked well
- Heavy Precast Pier Footings successfully placed using Floating Pier Installer despite strong river currents
- Sacrificial Hydraulic Jacks for levelling and use of green joint (above water) to ensure proper final alignment proved successful
- Specialized training required in Quebec for use of stainless steel rebar (rust staining, bar bending, contact between dissimilar materials, etc.)
- Development of special mixes were key in achieving a successful outcome (self-compacting concrete, ternary cement mixes, use of fly ash)
- Environmental protection presented key challenges – particularly during aquatic excavation to rock for marine footings (turbidity curtains, winter conditions)
- Institute for Sustainable Infrastructure (ISI) – targeting Envision Bronze Award, but higher Platinum Level Award achieved – under DB/PPP project delivery method – confirming that such requirements can be embedded within a PPP or DB contract



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

A Global Team




De Medellín para el mundo: Conectando
saberes, construyendo futuro

Effective Communication and Collaboration (Cloud Based)

TYLin

- Change management – Design Quality Plan
- Cloud-based electronic document control system accessible by all design team members from different entities
- Regular scheduled team meetings
- Communication protocols
 - multilingual team
- Quality training
- Expedited reviews and comment resolutions
- CADD integration
- Streamlined communication across different time zones

A Global Team Necessitates a Cloud-based Document Control System



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Credits

- Owner: Government of Canada
- Developer: Signature on the Saint Lawrence Group
- Contractor: Signature on the Saint Lawrence Construction (Partnership of SNC-Lavalin Major Project Inc., Dragados Canada Inc., and Flatiron Constructors Canada Limited)
- Designer: TYLI-IBT-SLI Joint Venture (JV of TYLin Canada Inc., Systra-International Bridge Technologies Canada Inc., and SNC-Lavalin)
- Owner Eng.: Arup Canada Inc.
- Independent Eng.: Stantec/ Ramboll
- Design Subconsultants: Akana (Cooper Zietz Engineers), Boundary Layer Wind Tunnel Laboratory at the University of Western Ontario, Doug Williams, Frieder Seible, Fugro Consultants, IFN Engineering, HLB (Illumination Arts), Karagozian & Case, MacDonald Architects, NC3D, Ross & Baruzzini, Tourney Consulting Group, WEST Consultants, West Wind Laboratory, WSP (MMM)



De Medellín para el mundo: Conectando
saberes, construyendo futuro

TYLin

Gracias!!



Credit: @ThomasHeinzer



De Medellín para el mundo: Conectando
saberes, construyendo futuro